



REQUEST FOR PROPOSAL

Solicitation No.: 325-069

Project Title:	Provision of Labor and Materials for the Repair of Second Floor Comfort Rooms and Replacement of Doors at BU College of Nursing		
ABC:	Five Hundred Thousand and 00/100 Pesos (₱ 500,000.00)	Fund Source:	Fund - 05
Mode of Procurement:	Negotiated Procurement under Small Value Procurement (Section 53.9)	Mode of Evaluation:	BY LOT
Implementing Office/ End-user/s:	BU College of Nursing PROF. FATIMA B. CALINGACION, Assoc. Dean	Delivery Period:	120 Days Upon Receipt of Letter Order (LO)
Required Document/s:	<div><input checked="" type="checkbox"/> Mayor's Permit</div> <div><input checked="" type="checkbox"/> PhilGEPS Registration Number</div> <div><input checked="" type="checkbox"/> DTI / SEC Registration</div> <div><input checked="" type="checkbox"/> Updated /Latest TAX Clearance</div> <div><input checked="" type="checkbox"/> Omnibus Sworn Statement Supported by Secretary Certificate <u>for CORPORATION</u> (if LCRB/SCRB and ABC is ₱ 50,000.00 Above);</div> <div><input checked="" type="checkbox"/> Special Power of Attorney <u>for PARTNERSHIP</u> if Authorizing his/her Partner or a Representative (if LCRB/SCRB and ABC is ₱ 50,000.00 Above);</div> <div><input checked="" type="checkbox"/> Special Power of Attorney <u>for SOLE PROPRIETORSHIP</u> if Authorizing a Representative (if LCRB/SCRB and ABC is ₱ 50,000.00 Above)</div>		

Sir/Madam:

Please quote your lowest price on the item/s listed below, subject to the Terms and Conditions provided in the last portion, stating the shortest time of delivery, and submit your quotation duly signed by your representative not later than **Aug 11, 2025 12:00 NN** sealed in an envelope. Failure to submit with this form the above-listed eligibility requirements with the check(☒) shall automatically disqualify the bids.


DENNIS A. LUNAS

BU Cluster 3 BAC Secretary



After having carefully read and accepted the Terms and Conditions, I/We submit our quotation/s for the item/s as follows:

ITEM	QTY	UOM	DESCRIPTION	ABC (PHP)	Compliance to Specifications		REMARKS	U/PRICE
					YES	NO		
	1	LOT	Labor and Materials for the Repair of Second Floor Comfort Rooms and Replacement of Doors	500,000.00				

SCOPE OF WORKS AND TECHNICAL SPECIFICATIONS

All works to be undertaken shall be in accordance with the plans and working drawings. It includes the furnishing of all materials, labor and equipment with supervision necessary for the complete construction of the said project.

The plans, detailed drawings and this scope of work shall be considered as complementing with each other, so that what is mentioned or shown on one, although not mentioned or shown in another, shall be considered as appearing in both. In case of conflict between the two, the same should be referred to the designing Architect/Engineer.

ITEMS OF WORK INCLUDED :

This program of work covers the replacement of ceiling, painting of doors and installation of aluminum doors at both Male and Female comfort room. Also included is the installation of aluminum partition on urinals and installation of Water Pump system and some plumbing fixtures.

I. GENERAL REQUIREMENTS

1.00 lot

This item of work includes the fabrication and installation of Project Sign Boards, Temporary Utilities, Stock Room and Enclosure including the 2 months of electrical power consumption, and the provisions for the General Health and Safety Program.

II. SITE WORKS

1.00 lot

This item of work includes the following site works:

a. Cleaning and clearing of site before and after construction	1.00	lot
b. Dismantling and removal of existing ceiling at 2F Male and Female CR	17.00	sq.m.
c. Dismantling of existing doors at 2nd Floor Male and Female CR	5.00	sets
d. Dismantling of existing classroom doors	9.00	sets
e. Removal of Drainage Pipes and Water Line on Lavatory	1.00	lot
f. Dismantling and replacement of electrical wires and electrical fixtures	1.00	lot
g. Hauling of construction materials and waste material	1.00	lot

Also included is the equipment rental of hauling truck and other equipment needed to complete the said item of work. Confer with the Supply Officer as to the designated area where the waste materials are to be stockpiled. The contractor shall submit the waste material prior to demobilization.

III. CEILING WORKS

17.00 sq.m

This item of work includes the furnishing and installation of 3.5mm thk. Ficem Board on 0.4mm x 1" x 2" x 16' Metal furring with ceiling joist spaced @ 600mm x 600mm on center bothways. Use 5/32"Ø x 1/2" Blind Rivets for anchorage of joints and 1.0" x 1.0" x 0.5mm x 3m wall angle on concrete wall perimeter anchored by 10mm dia. x 2" expansion bolt w/ shield. Use 0.4mm x 1" x 2" x 16' metal furring as hangers. Use 3" Wooden Cornice x 2.4m.

Use welding rod, level hose, nylon and other miscellaneous hardware items necessary for the completion of work.



continuation...

ITEM	QTY	UOM	DESCRIPTION	ABC (PHP)	Compliance to Specifications		REMARKS	U/PRICE
					YES	NO		
			Labor and Materials for the Repair of Second Floor Comfort Rooms and Replacement of Doors					

SCOPE OF WORKS AND TECHNICAL SPECIFICATIONS

Also included is the equipment rental of one Drill Tool & Drill Bits, and Cutting tools & blade needed to finish the said item of work.

It is necessary to use cutting tools & blade for cutting rods and wall angles.

All materials shall be approved high quality.

Please refer to the Ceiling Plan for complete details.

IV. PAINTING WORKS

29.00 sq.m.

This item of work includes the painting of the following:

A. Door at 2F Male and Female CR

12.00 sq.m.

Use Flat Enamel Paint (1 coat), Interior Semi-Gloss Enamel (2 coats), Exterior Gloss Enamel (2 coats), Glazing Putty, and Tinting Color to wood surfaces.

B. Ceiling

17.00 sq.m.

Use Flat Latex undercoat (1 coat), Patching Compound, and Flat Latex topcoat (2 coats) to ficem board surfaces.

This item of work includes the use of sandpaper, paint rollers, brushes, tray, rags, newspapers and other miscellaneous item to finish the painting works.

The painting contractor shall supply all labor, tool and equipment necessary and shall perform all painting and finishing works as shown in the schedule of painting and other surfaces to render ready to use.

Painting materials shall be stored in one place in the building to be kept neat and clean.

Before any painting is done all surfaces shall be cleaned, smoothed and free from dust. Dirt, grease, mortar, rust and other foreign substances and all parts where paint remover has been used shall be washed off with paint or laquer thinner.

All paints shall be spread evenly and carefully.

No painting shall be done on outside work extremely cold, frosty, foggy or damp weather.

All materials shall be approved high quality.

V. DOORS AND PARTITION

19.00 sets

This item of work includes fabrication and installation of the following:

For Replacement of broken and damaged doors

D01 0.70m x 1.60m Aluminum (Powder Coated) Swing Door Type w/ Heavy-Duty Lockset Complete with accessories **5.00 sets**

D02 0.90m x 2.10m Steel Type Door with viewing window and fixed glass transom w/ Heavy-Duty Lockset Complete with accessories (painting is included) **9.00 sets**

Stainless Steel Door Knob (for entrance Door at Male & Female CR) **2.00 sets**

PARTITION

For installation of new partition on Urinals

P01 0.40m x 1.00m Aluminum Partition w/ complete accessories **3.00 sets**

All materials shall be approved high quality.

Please refer to the Plan for complete details.



continuation...

ITEM	QTY	UOM	DESCRIPTION	ABC (PHP)	Compliance to Specifications		REMARKS	U/PRICE
					YES	NO		
			Labor and Materials for the Repair of Second Floor Comfort Rooms and Replacement of Doors					

SCOPE OF WORKS AND TECHNICAL SPECIFICATIONS

VI. PLUMBING WORKS

1.00 lot

This item of work includes the furnishing and installation of the following plumbing fixtures and materials:

A. Plumbing Fixtures and Fittings

Water Closet Set (w/complete accessories)	1.00	set
Lavatory Drain Pipe Set w/ P-Trap (stainless steel or heavy duty)	5.00	sets
Lavatory Water Pipe Set (Flexible hose, angle bar, etc.)	5.00	sets
Vanity Mirror	5.00	sets
Miscellaneous Items (teflon tape, pipe, fittings, etc)	1.00	lot

B. Water Pressure System

Materials for Pump House (W-1.4m, L-1.7m, H-1.5m) and tapping of water line to source:

Portland Cement	10.00	bags
Gravel	0.50	cu.m.
Washed Sand	1.00	cu.m.
Ordinary CHB 4" Thk	98.00	pcs
10mm dia x 6m RSB	25.00	pcs
12mm dia x 6m RSB (Fabricated door)	5.00	pcs
GI Tie Wire	1.00	kg
Heavy duty padlock w/ key	1.00	unit
1 HP Booster Pump	1.00	unit
42 gal Pressure Tank (Stainless 304)	1.00	unit
600 Liter Stainless Steel Cylindrical Water Storage Tank	1.00	unit
Magnetic switch	1.00	unit
Electric Floating Switch	1.00	unit
Pressure Gauge	1.00	unit
1" Ø PN-25 PPR gate valve	2.00	sets
1" Ø PN-25 PPR union	3.00	pcs
1" Ø x 90 deg PN-25 PPR elbow	4.00	pcs
1" Ø PN-25 PPR male adaptor	3.00	pcs
1" Ø x 1" Ø PN-25 PPR tee	4.00	pcs
1" Ø x 1" Ø GI Tee	2.00	pcs
1/4" Ø x 3" Ø GI Nipple	5.00	pcs
1/4" Ø x 1/4" Ø GI Tee	2.00	pcs
1 1/4" x 1" Ø bushing reducer	2.00	pcs
1" Ø x 3/4" Ø bushing reducer	2.00	pcs
3/4" Ø x 1/4" Ø bushing reducer	2.00	pcs
1 1/4" x 1" Ø PN-25 PPR coupling reducer	5.00	pcs
1" Ø PN-25 PPR coupling	5.00	pcs
1" Ø PN-25 PPR Swing valve	1.00	set

VIII. ELECTRICAL WORKS

1.00 lot

This item of works includes rewiring of existing CR lighting fixtures and switches. For power supply use 2-3.5 sq. mm THHN wire in 20 mm dia., flexible hose and mica tube.

This also includes installation of power supply for one (1) unit Booster pump. Power supply will be tapped at existing Panelboard spare.



continuation...

ITEM	QTY	UOM	DESCRIPTION	ABC (PHP)	Compliance to Specifications		REMARKS	U/PRICE
					YES	NO		
			Labor and Materials for the Repair of Second Floor Comfort Rooms and Replacement of Doors					

SCOPE OF WORKS AND TECHNICAL SPECIFICATIONS

Use 2-5.5 sq. mm THHN wire + 1-5.5 sq. mm THHN wire (green) in PVC 20 mm dia conduit.

Also includes miscellaneous items to complete the installation

See electrical plan for directives.

See below stated bill of materials

Replacement of CR lighting fixtures

Round downlight with built in 12W daylight ultra thin, flush mounted	6.00	sets
One gang switch	2.00	sets
Electrical tape	1.00	Rolls
Junction box with cover	6.00	pcs
Mica tube 1/4"	6.00	meters
3.5mm ² THHN wire (red and white)	50.00	meters
Flexible conduit 20 mm dia	20.00	meters
Other miscellaneous and consumables	1.00	lot

Booster Pump power supply

5.5mm ² THHN wire (red and white)	100.00	meters
5.5mm ² THHN wire (green)	50.00	meters
30AT Enclosed circuit breaker, 2P, 230V in nema 3r enclosure	1.00	set
30AT circuit breaker only, 2P, 230V (same specs as existing to be tapped at spare		
PVC conduit 20 mm dia conduit	18.00	pcs
PVC 20 mm dia c-clamp	54.00	pcs

VIII. FORMWORKS AND SCAFFOLDINGS

1.00 lot

This item of work includes the furnishing and installation of 2 pcs of 1/2" thk Ordinary Plywood , 5 pcs of 2"x 3" x 12' Coco Lumber, and 5 pcs of 2"x 2" x 12' Coco Lumber, G.I. Tie Wire # 16 and assorted CW nails for scaffolding and bracing to complete the said item of work.

BILL OF MATERIALS AND COST ESTIMATES

I. GENERAL REQUIREMENTS

1.00 lot

PART A

Project Sign Boards	1.00	each	@	3,000.00 / lot		3,000.00
Temporary Utilities, Stock Room and Enclosure	1.00	lot	@	10,000.00 / lot	P	10,000.00
				(A) Direct Cost	P	13,000.00
				(B) Indirect Cost		3,250.00
				Vat (5% of A & B)		812.50
				SUB COST I-A	P	17,062.50

PART B

General Health and Safety Program	1.00	lot	@	2,000.00 / lot		2,000.00
Water and Electrical Power Consumption	2.00	mos.	@	1,000.00 / mos.		2,000.00
				(A) Direct Cost	P	4,000.00
				Vat (5% of A & B)		200.00
				SUB COST I-B	P	4,200.00
				ITEM COST I	P	21,262.50



continuation...

ITEM	QTY	UOM	DESCRIPTION	ABC (PHP)	Compliance to Specifications		REMARKS	U/PRICE
					YES	NO		
			Labor and Materials for the Repair of Second Floor Comfort Rooms and Replacement of Doors					

BILL OF MATERIALS AND COST ESTIMATES

II. SITE WORKS

a. Cleaning and clearing of site before and after construction	1.00	lot						
b. Dismantling and removal of existing ceiling at 2F Male and Female CR	1.00	lot	@	3,000.00	/	lot		3,000.00
c. Dismantling of existing doors at 2nd Floor Male and Female CR	17.00	sq.m.	@	150.00	/	sq.m.		2,550.00
d. Dismantling of existing classroom doors	5.00	sets	@	350.00	/	set		1,750.00
e. Removal of Drainage Pipes and Water Line on Lavatory	9.00	sets	@	350.00	/	set		3,150.00
f. Dismantling and replacement of electrical wires and electrical fixtures	1.00	lot	@	1,500.00	/	lot		1,500.00
g. Hauling of construction materials and waste material	1.00	lot	@	2,500.00	/	lot		2,500.00

Equipment Rental:

Hauling truck	1.00	day	@	8,136.00	/	day		8,136.00
				(A) Direct Cost			P	25,086.00
				(B) Indirect Cost				6,271.50
				Vat (5% of A & B)				1,567.88
				ITEM COST II			P	32,925.38

III. CEILING WORKS

Materials

3.5mm thk. Ficem Board	7.00	pcs	@	430.00	/	pc		3,010.00
Metal furring, 0.4mm x 1" x 2" x 16'	13.00	pcs	@	190.00	/	pc		2,470.00
Wall Angle, 1.0" x 1.0" x 0.5mm x 3m	10.00	pcs	@	90.00	/	pc		900.00
5/32"Ø x 1/2" Blind Rivets	350.00	pcs	@	3.00	/	pc		1,050.00
10mm dia. X 2" expansion bolt w/ shield	33.00	pcs	@	42.00	/	pc		1,386.00
Metal furring, 0.4mm x 1" x 2" x 16' (hangers)	14.00	pcs	@	190.00	/	pc		2,660.00
3" Wooden Cornice x 2.4m	11.00	pcs	@	300.00	/	pc		3,300.00
Welding Rod	0.50	kg	@	150.00	/	kg		75.00
Level hose, nylon, Mesh Tape, Miscellaneous Hardware items	1.00	lot	@	800.00	/	lot		800.00
				Material Cost			P	15,651.00
				Labor Cost				5,477.85

Equipment Rental

Drill Tool & Drill Bits	2.00	days	@	650.00	/	days		1,300.00
Cutting Tool & Blade	2.00	days	@	800.00	/	days		1,600.00
				Equipment Rental Cost				2,900.00
				(A) Direct Cost			P	24,028.85
				(B) Indirect Cost				6,007.21
				Vat (5% of A & B)				1,501.80
				ITEM COST IV			P	31,537.87

IV. PAINTING WORKS

Materials

A. Door at 2F Male and Female CR	29.00	sq.m.						
Flat Enamel Paint (1 coat)	12.00	sq.m.						
Interior Semi-Gloss Enamel (2 coats)	1.00	liter	@	200.00	/	liter		200.00
Exterior Gloss Enamel (2 coats)	1.00	liter	@	220.00	/	liter		220.00
Glazing Putty	1.00	liter	@	220.00	/	liter		220.00
Tinting Color	1.00	liter	@	180.00	/	liter		180.00
sandpaper, paint rollers, brushes, tray, rags & newspapers	1.00	can	@	135.00	/	can		135.00
	1.00	lot	@	300.00	/	lot		300.00
B. Ceiling	17.00	sq.m						
Flat Latex undercoat (1 coat)	1.00	liter	@	200.00	/	gal		200.00
Patching Compound	1.00	kg	@	80.00	/	kg		80.00
Flat Latex topcoat (2 coats)	2.00	liter	@	200.00	/	gal		400.00
meshtape, sandpaper, paint rollers, brushes, tray, rags & newspapers	1.00	lot	@	500.00	/	lot		500.00

Labor

	1.00	lot	@	852.25	/	lot		852.25
				Material Cost			P	2,435.00
				Labor Cost				852.25
				(A) Direct Cost			P	3,287.25
				(B) Indirect Cost				821.81
				Vat (5% of A & B)				205.45



continuation...

ITEM	QTY	UOM	DESCRIPTION	ABC (PHP)	Compliance to Specifications		REMARKS	U/PRICE
					YES	NO		
			Labor and Materials for the Repair of Second Floor Comfort Rooms and Replacement of Doors					

BILL OF MATERIALS AND COST ESTIMATES

				ITEM COST VII		P	4,314.52
V. DOORS AND PARTITION				19.00	sets		
DOORS							
<i>For Replacement of broken and damaged doors</i>							
D01	0.70m x 1.60m Aluminum (Powder Coated) Swing Door Type w/ Heavy-Duty Lockset Complete with accessories			5.00	sets	@	36,400.00
D02	0.90m x 2.10m Steel Type Door with viewing window and fixed glass transom w/ Heavy-Duty Lockset Complete with accessories (painting is included)			9.00	sets	@	110,565.00
	Stainless Steel Door Knob (for entrance Door at Male & Female CR)			2.00	sets	@	1,200.00
PARTITION							
<i>For installation of new partition on Urinals</i>							
P01	0.40m x 1.00m Aluminum Partition w/ complete accessories			3.00	sets	@	7,800.00
Labor				1.00	lot	@	23,394.75
						Material Cost	155,965.00
						Labor Cost	23,394.75
						(A) Direct Cost	179,359.75
						(B) Indirect Cost	44,839.94
						Vat (5% of A & B)	11,209.98
						ITEM COST V	235,409.68
VI. PLUMBING WORKS				1.00	lot		
Materials							
A. Plumbing Fixtures and Fittings				1.00	lot		
	Water Closet Set (w/complete accessories)			1.00	set	@	7,500.00
	Lavatory Drain Pipe Set w/ P-Trap (stainless steel or heavy duty)			5.00	sets	@	3,250.00
	Lavatory Water Pipe Set (Flexible hose, angle bar, etc.)			5.00	sets	@	2,500.00
	Vanity Mirror			5.00	sets	@	2,750.00
	Miscellaneous Items (teflon tape, pipe, fittings, etc)			1.00	lot	@	500.00
B. Water Pressure System				1.00	lot		
<i>Materials for Pump House (W-1.4m, L-1.7m, H-1.5m) and tapping of water line to source:</i>							
	Portland Cement			10.00	bags	@	2,700.00
	Gravel			0.50	cu.m.	@	550.00
	Washed Sand			1.00	cu.m.	@	550.00
	Ordinary CHB 4" Thk			98.00	pcs	@	1,176.00
	10mm dia x 6m RSB			25.00	pcs	@	4,125.00
	12mm dia x 6m RSB (Fabricated door)			5.00	pcs	@	900.00
	GI Tie Wire			1.00	kg	@	90.00
	Heavy duty padlock w/ key			1.00	unit	@	600.00
	1 HP Booster Pump			1.00	unit	@	11,000.00
	42 gal Pressure Tank (Stainless 304)			1.00	unit	@	7,500.00
	600 Liter Stainless Steel Cylindrical Water Storage Tank			1.00	unit	@	20,505.00
	Magnetic switch			1.00	unit	@	850.00
	Electric Floating Switch			1.00	unit	@	1,500.00
	Pressure Gauge			1.00	unit	@	350.00
	1" Ø PN-25 PPR gate valve			2.00	sets	@	1,600.00
	1" Ø PN-25 PPR union			3.00	pcs	@	1,590.00
	1" Ø x 90 deg PN-25 PPR elbow			4.00	pcs	@	152.00
	1" Ø PN-25 PPR male adaptor			3.00	pcs	@	1,350.00
	1" Ø x 1" Ø PN-25 PPR tee			4.00	pcs	@	220.00
	1" Ø x 1" Ø GI Tee			2.00	pcs	@	80.00
	1/4" Ø x 3" Ø GI Nipple			5.00	pcs	@	140.00
	1/4" Ø x 1/4" Ø GI Tee			2.00	pcs	@	80.00
	1 1/4" x 1" Ø bushing reducer			2.00	pcs	@	120.00
	1"Ø x 3/4" Ø bushing reducer			2.00	pcs	@	70.00
	3/4"Ø x 1/4" Ø bushing reducer			2.00	pcs	@	60.00
	1 1/4" x 1" Ø PN-25 PPR coupling reducer			5.00	pcs	@	325.00
	1" Ø PN-25 PPR coupling			5.00	pcs	@	140.00



continuation...

ITEM	QTY	UOM	DESCRIPTION	ABC (PHP)	Compliance to Specifications		REMARKS	U/PRICE
					YES	NO		
			Labor and Materials for the Repair of Second Floor Comfort Rooms and Replacement of Doors					

BILL OF MATERIALS AND COST ESTIMATES

1" Ø PN-25 PPR Swing valve

1.00	set	@	722.00 / set		722.00
			Material Cost:	P	75,545.00
1.00	lot	@	26,440.05 / lot		26,440.05
			Labor Cost:	P	26,440.05
			(A) Direct Cost	P	101,985.05
			(B) Indirect Cost		25,496.26
			Vat (5% of A & B)		6,374.07
			ITEM COST VI	P	133,855.39

Labor

VII. ELECTRICAL WORKS

1.00 lot

Replacement of CR lighting fixtures

Round downlight with built in 12W daylight ultra thin, flush mounted
 One gang switch
 Electrical tape
 Junction box with cover
 Mica tube 1/4"
 3.5mm² THHN wire (red and white)
 Flexible conduit 20 mm dia
 Other miscellaneous and consumables

6.00	sets	@	700.00 / set		4,200.00
2.00	sets	@	200.00 / set		400.00
1.00	Rolls	@	50.00 / roll		50.00
6.00	pcs	@	50.00 / pc		300.00
6.00	meters	@	30.00 / m		180.00
50.00	meters	@	37.00 / m		1,850.00
20.00	meters	@	15.00 / m		300.00
1.00	lot	@	500.00 / lot		500.00

Booster Pump power supply

5.5mm² THHN wire (red and white)
 5.5mm² THHN wire (green)
 30AT Enclosed circuit breaker, 2P, 230V in nema 3r enclosure
 30AT circuit breaker only, 2P, 230V (same specs as existing to be tapped at spare)
 PVC conduit 20 mm dia conduit
 PVC 20 mm dia c-clamp

100.00	meters	@	60.00 / m		6,000.00
50.00	meters	@	60.00 / m		3,000.00
1.00	set	@	1,500.00 / set		1,500.00
18.00	pcs	@	90.00 / pc		1,620.00
54.00	pcs	@	3.00 / pc		162.00
			Material Cost:	P	20,062.00

Labor

1.00	lot	@	7,021.70 / lot		7,021.70
			Labor Cost:	P	7,021.70
			(A) Direct Cost	P	27,083.70
			(B) Indirect Cost		6,770.93
			Vat (5% of A & B)		1,692.73
			ITEM COST VII	P	35,547.36

VIII. SCAFFOLDINGS

Materials

1/2" thk Ordinary Plywood -
 2"x 3" x 12' Coco Lumber -
 2"x 2" x 12' Coco Lumber -
 G.I. Tie Wire # 16 -
 Assorted CW Nails -

1.00 lot

2.00	pcs		720.00 / pc		1,440.00
5.00	pcs		156.00 / pc		780.00
5.00	pcs		104.00 / pc		520.00
0.50	kg		90.00 / kg		45.00
1.00	kg		120.00 / kg		120.00

Labor

			Material Cost	P	2,905.00
1.00	lot	@	1,016.75 / lot		1,016.75
			Labor Cost		1,016.75
			(A) Direct Cost	P	3,921.75
			(B) Indirect Cost		980.44
			Vat (5% of A & B)		245.11
			ITEM COST VIII	P	5,147.30

GRAND SUMMARY

I. GENERAL REQUIREMENTS				P	21,262.50
II. SITE WORKS					32,925.38
III. CEILING WORKS					31,537.87
IV. PAINTING WORKS					4,314.52
V. DOORS AND PARTITION					235,409.68
VI. PLUMBING WORKS					133,855.39
VII. ELECTRICAL WORKS					35,547.36
VIII. SCAFFOLDINGS					5,147.30
Approved Budget for Contract				P	500,000.00



continuation...

ITEM	QTY	UOM	DESCRIPTION	ABC (PHP)	Compliance to Specifications		REMARKS	U/PRICE
					YES	NO		
			Labor and Materials for the Repair of Second Floor Comfort Rooms and Replacement of Doors					

BILL OF MATERIALS AND COST ESTIMATES

GRAND SUMMARY		
I. GENERAL REQUIREMENTS	P	21,262.50 ✓
II. SITE WORKS		32,925.38 ✓
III. CEILING WORKS		31,537.87 ✓
IV. PAINTING WORKS		4,314.52 ✓
V. DOORS AND PARTITION		235,409.68 ✓
VI. PLUMBING WORKS		133,855.39 ✓
VII. ELECTRICAL WORKS		35,547.36 ✓
VIII. SCAFFOLDINGS		5,147.30 ✓
Approved Budget for Contract		P 500,000.00 ✓

Nothing follows...

Delivery Compliance:	<input type="radio"/> YES	<input type="radio"/> NO	TOTAL BID PRICE:
Payment Term:			Price Validity:

Printed Name / Signature

Tax Identification Number (TIN) / Tax Type

Contact Number

Email Address

TERMS & CONDITIONS

- 1 All entries must be typewritten or in BLOCK LETTERS;
- 2 Bidders shall provide the correct and accurate information required in this form.
- 3 The following shall be observed in accomplishing the Quotation/Proposal forms:

ITEM	QTY	UOM	DESCRIPTION	ABC (PHP)	Compliance to Specifications		REMARKS	U/PRICE
					YES	NO		
1							②	③
Delivery Compliance:				TOTAL BID PRICE: ④				
Payment Term:				Price Validity:				

1. Check or put COMPLIED / NOT COMPLIED in the "YES" or "NO" if compliant with the specifications or not;
2. State the brand/model offered and/or alternate offer if checked "NO" or NOT COMPLIED in the compliance;
3. State the Unit Price in accordance with the UOM;
4. State the TOTAL Bid Price for all items with the bid.

- 4 Detailed literature or brochure of the offer, as may be applicable, shall be submitted to support the statement of compliance with the technical specifications;
- 5 Price quotation/s must be valid for a period of **45 CALENDAR DAYS** from the submission date.
- 6 Price quotation/s, to be denominated in Philippine peso shall include all taxes, duties, and/or levies payable, and quotations exceeding the Approved Budget for the Contract shall be rejected.
- 7 **Cash on Delivery (C.O.D.) as payment term is not allowed per agency Accounting Policy.**
- 8 Bids with no Payment Term and/or Delivery Term indicated shall be understood to be in adherence with the standard Government Terms and/or conditions stipulated in these forms;
- 9 Award of the contract shall be made to the lowest quotation that complies with the minimum technical specifications and other terms and conditions stated herein;
- 10 Proposal/Quotation forms issued by the designated canvasser or those acquired electronically, either downloaded from the BU website or the PhilGEPS or requested through e-mail, shall bear the original signature over the printed name of the authorized
- 11 Submission of proposal/quotation forms through e-mail shall be allowed, specifically for suppliers outside the Province of Albay, provided that the original signed forms shall be transmitted to the CS-BAC Secretariat through courier; non-receipt of which shall
- 12 Any interlineations, erasures, or overwriting shall be valid only if they are signed or initialed by you or any of your duly authorized representative/s;
- 13 The document requirements which shall be submitted with the proposals/quotations shall be per Annex "H", Appendix A (*Documentary Requirement for Alternative Methods of Procurement*) of the 2016 IRR of R.A. 9184; the notarized Omnibus Sworn Statement shall be submitted by winning bidder (for ABC's above ₱ 50,000.00);
- 14 Proposals and documents shall be submitted to the following address:

The BU Cluster 3 BAC Chairperson
BU Cluster 3 BAC Secretariat Office,
BU College of Science Bldg. 4, BU Main Campus, Legazpi City
Contact No.: 0985 801 6645
Email: bu-cluster3bac@bicol-u.edu.ph

- 15 The Bicol University-BAC shall have the right to inspect and/or test the goods to confirm their conformity to the technical requirements.
- 16 Implementation of the project shall follow the provisions of the Revised Rules and Regulations of R.A. 9184.